

Technical Specifications Sapphire in Ag. Athanasios

1. PRELIMINARY WORKS

- a. Liability for all build permissions
- **b.** Lining of the constructions
- c. Quality control
- **d.** Preparation of contracts
- e. Supervision from qualified Architect
- f. Clean less to prepare the apartments to be delivered

2. EARTHWORKS

a. Earthworks according the plans to ensure all the finish levels inclusive compaction, compressor etc.

3. STRUCTURE

a. The tunnel system form is applied for the construction of the structure. Continuous vertical reinforced concrete columns together with horizontal reinforced concrete slaps, form a monolithic structure with anti-seismic abilities according to drawings.

4. WALLING

- a. External walls are constructed with 250mm thick
- b. Internal walls are constructed with 100mm thick,

5. PLASTERING

- a. Internal walls are rendered with three coats of cement mortar
- b. External walls are insulated with polystyrene according to energy study

6. WALL FINISHES

- a. External walls are decorated with grafiato; color according to the designers/architect's preference.
- b. Internal walls are decorated with three coats of spatula and emulsion paint; color According to clients preference



7. FLOORING

- a. Living Room Dining room & entry hall: Best quality tiles or ceramic €20 per sq.m (including Vat.)
- b. Bedroom: tiles €20 per sq.m (including Vat.)
- c. Kitchen: Best quality tiles €20 per sq.m (including Vat.)
- d. Verandas: Best quality tiles €20 per sq.m (including Vat.)
- e. bathrooms: Ceramic tiles €20 per sq.m (including Vat.)
- f. Common areas: Architects/designers preference
- g. Storage rooms: Architects/designers preference
- h. All dimensions of the tiles should be 60 cm x 60cm or 60cm x 120cm.

8. WALL TILES

- a. kitchen: granite € 250 per meter
- b. bathrooms: Ceramic tiles €20 per sq.m all around up to ceilings (including Vat.)
- c. All dimensions of the tiles should be 60 cm x 60cm or 60cm x 120cm.

9. DOORS AND WINDOWS

- a. Building main entrance door 1,200€ including Vat
- b. Apartments main entrance doors embossed melamine fire resistance (all doors will be the same according to the designers/architects preference)
- c. All apartment internal doors made of embossed melamine 400€ per door
- d. handles €25 each plus vat
- e. All external doors and windows are with aluminum series MU 114 (color *according to the designers/architects preference*)
- f. Glass will be thermal
- q. Provision for mosquito nets

10. WARDROBES AND KITCHEN UNITS

- a. Kitchen unit: 220 euros per running meter
- b. Granit for kitchen top 250 euros per meter
- c. Wardrobes with doors: 220 euros per m²

11. SANITARY WARE FITTINGS

a. Bathtub, W/C, washbasin, mixed taps, fittings, kitchen – composite double sink €2,500 including Vat for the 2 bedroom apartment and 1,700€ including vat for 1 bedroom apartments



12. PLUMBING-DRAINAGE

a. Hot & Cold-water installation includes plastic storage tanks high-pressure system (pipe in pipe). Complete Solar system.

13. ELECTRICAL

a. It includes an adequate number of lighting power, TV, telephone points bell and cooker control. Lighting fittings are not included. All according Drawing. (extra electrical points may be subject to extra charge accordingly)

14. AIR CONDITIONING

a. Provisions only for hot and cold a/c

15.INSULATIONS

a. According to thermal insulation study

16. LIFT

a. Choice of the contractor/architect/designer

17. PARKING AREA

- a. Will be made by painted concrete
- b. Parking Bar or Gate with remote control

18. ENTRANCE

a. CCTV camera door phone for each apartment with code for entering and 2 cards

& CONSTRUCTI

- b. 2 keys for each apartment
- c. Gated entrance

19. PHOTOVOLTAICS

a. 2KW Included

20.GYM AREA

a. Common gym area for all apartments

21.LANDSCAPING

- a. Tree planting
- b. All 3D pictures that are advertised are indicative and are subject to change concerning the exterior color shades.

Email: info@pg-constructions.com